



# Boddington Community Yarning Circle Project 2026

List of Community contributions  
materials and equipment

# Materials

## 1. Ground logs and timber seating stumps

Description: Jarrah and/or Wandoo; solid section, no stress cracks from felling; seasoned

Size: Approx. 3.5 – 5m long; diameter 600 – 900mm

Shape: Curved and forked where possible

Quantity: 38



## 2. Vertical timber totem poles and fixing poles

Description: Jarrah and/or Wandoo; solid section, no stress cracks from felling; seasoned

Size: Approx. 3.0 – 4.5m long; diameter 200 – 400mm

Shape: Curved and forked where possible

Quantity: 20



## 3. Timber giant way-markers

Description: Jarrah and/or Wandoo; solid section, no stress cracks from felling; seasoned

Size: Approx. 3.5 – 5m long; diameter 800 – 1500mm

Shape: Feature log

Quantity: 6



## 4. Stone & Earthworks Materials

Rocks – seating and landscape features

Material: Selected granite or laterite

Size 1:

- Approx. 500 × 500mm
- Preferred one flat face
- Quantity: 120

Size 2:

- Approx. 800 × 1400mm
- Preferred one flat face
- Quantity: 80



## 5. Clean fill

Description: Clean fill for creating raised planter bed mounds; suitable for planting; contaminant free

Amount: Approx. 192m<sup>3</sup>

## 6. Compacted pathway materials

Description: Compacted graded laterite fines and compacted summer stone fines; contaminant free

Amount: Approx. 35m<sup>3</sup>



## 7. Selected mulch

Description: Selected and graded ground mulch; no large splinter pieces; composted; contaminant and weed free

Amount: Approx. 65m<sup>3</sup>



## 8. Plants

Native shade canopy trees:

- Approx. 5–6m mature height (e.g. *Eucalyptus victrix*)
- Quantity: 15 (45 – 90L pots)

Bush tucker and bush medicine plants:

- Quantity: 150 (1L pots)



## 9. Reticulation

Description: Reticulation for approx. 330m<sup>2</sup> of planted native garden area

## 10. Concrete

Description: Concrete for footings to vertical timbers, signage and core ten screens

Amount: Approx. 10m<sup>3</sup>

## 11. Hardware

12mm and 16mm galvanised threaded rod, nuts and washers

- Amount: Approx. 10m

12mm and 16mm galvanised coach screws

- Lengths 150 – 300mm
- Quantity: Approx. 80

## 12. Machinery

- Large loader (approx. 1.5 tonne capacity) to move rocks and scalp site
- Compactor
- Cement mixer
- Fire-fighting trailer